



Installation manual

A1140 three-phase meter WC or CT & LDC



Orsis

Clarendon House
Victoria Avenue
Harrogate
HG1 1JD
United Kingdom

General Enquiries
info@orsis.co.uk


Sales
sales@orsis.co.uk

Phone
01423 530700

Before installing an A1140 meter and LDC, Orsis advise carrying out an LDC GPRS connection check.


Elster A1140 three-phase whole current meter and LDC wiring diagram

Three-phase connection




Elster A1140 single-phase whole current meter and LDC wiring diagram.

Single-phase connection



Elster A1140 WC wiring schematic



3 phase 4 wire, Direct connected

RJ11 socket location



RJ11 Socket

Single-phase installation

A1140 LDC installation diagram.

Fit the LDC, RF and GPRS antenna.

Connect the antenna terminations to the LDC – left side is RF, right side is GPRS.

There are a selection of antennas which may be fitted depending upon signal strength and fitting space.


The small angled antenna should be fitted as first option.

Connect the LDC to the meter via the meter's RJ11 socket. LDC will now power up. The green LED in top right hand corner will illuminate.


Three-phase WC Elster A1140 and LDC with RF antenna.



Elster A1140 three-phase CT and LDC diagram



Elster A1140 CT wiring schematic



3 phase 4 wire, CT operated

RJ11 socket location



RJ11 Socket

UNDER NO CIRCUMSTANCES MAY THE SECONDARY CIRCUIT OF A CT BE OPENED WHEN CURRENT IS FLOWING IN THE PRIMARY CIRCUIT.

The voltage in an un-terminated secondary winding can reach several thousand volts in a fraction of a second if it is made open-circuit while current is flowing in the primary circuit being metered. Such high voltages can be extremely dangerous to personnel and can cause serious damage to the transformer or equipment connected to it. Such damage may not be immediately obvious, but will certainly lead to incorrect operation of the equipment.

POLARITY

CTs are direction sensitive and must be fitted the correct way round. CTs are marked with P1 and P2 to indicate which way they should be fitted around the cable or bus-bar. The side marked P1 must point towards the supply, and P2 must point towards the load. If an arrow is printed on the CT it must point towards the load.

The CT outputs - “secondary’s” - must be connected to the meter the correct way round. CTs are supplied with secondary terminals marked S1 and S2 which must be connected to the correct terminals on the meter. The meter will not register correctly if any of the CTs are connected incorrectly.

The CTs must be connected to the correct phase inputs on the meter.

Common secondary leads

For a three-phase circuit where two or three CTs are used, it is common practice to use one wire as the common secondary lead for all the CTs. This saves time and material and simplifies the wiring. The connections required depend on the type of supply being metered.


Grounding

It is common practice in low voltage (LV) installations (circuits below 1000 V) to ground the current transformer secondary **S2** leads. This is a safety precaution to protect against static voltages or insulation failure. There only needs to be one ground on the secondary circuit, and this is usually made at the transformer end (see diagram below). In three phase installations where a common secondary lead is used, the grounding can be taken from the common lead.

For correct operation it is essential that the CT's are connected the right way round and that the phase relationships are maintained between the meter and the CTs.

The following must be checked during installation of the meter and CTs:

1. Orientation of each CT around the conductor. (**P1** towards the generator, **P2** towards the load, or arrow pointing from the generator towards the load).
2. Output orientation from CT. (**S1** to 'current in', **S2** to 'current out').
3. CT assignment. (CT around L1 conductor connected to the L1 current inputs on the meter, and so on).



Using A1140 for PV export metering

Guidelines for wiring electricity meters for import and export metering


These are helpful guidelines for meter installers to assist with the wiring setup for generation and import/export metering. Where Orsis have supplied meters and meter reading services, it is the responsibility of the meter installer to ensure the installation, maintenance and security of the meter is dealt with safely and properly.

Export metering with three-phase CT meters

With modern three-phase electricity meters, the meter is capable of measuring energy in both energy flow directions. The Elster A1140 is a typical three-phase CT operated meter used in many micro-generation and import/export metering applications.

When using split core clip type CTs, it is important that the electrical orientation of the wires and the physical orientation of the CTs are correct. All 3 CTs should be wired in the same electrical and physical orientation.

Three phase 4 wire wiring diagram for the Elster A1140



Electrical wiring installation

Split core CTs come with 1 metre leads, a positive (red) and negative (black) cable. For phase A the positive lead should go into terminal 1 and the negative into terminal 3. The reference voltage for this phase goes into terminal 2 which is the small terminal block between 1 and 3.

There is an arrow on the CT to indicate which way round the cable it should go. The physical orientation is different depending if the meter is being used as a generation meter or as an import/export meter.

Wiring guidelines for Elster A1140 three-phase 4 wire meters

Terminal	
1	Element 1 - Line in - Voltage terminal - Line out
2	
3	
4	Element 2 - Line In - Voltage Terminal - Line Out
5	
6	
7	Element 3 - Line In - Voltage Terminal - Line Out
8	
9	
10	Neutral In Neutral Out
12	
Auxiliary	20 positive 21 negative

LDC initialisation and operational activity

After connecting the LDC to the A1140 meter and reconnection of supply, the LDC **PWR** LED will illuminate and the display will show the following information:

This LDC is the “DC voltage” powered version and gets its power from the A1140 meter.

After connecting the LDC and energising the supply to the meter, the LDC **PWR** LED will illuminate and the display will show the following information **(this may take up to five minutes)**:



At this point the LDC is connected and working



The LDC will now start looking for upgrades - you may see sending, receiving or upgrading. This is normal - during this time the LDC will turn itself on and off.

The display can show a number of scenarios after 5 minutes

“G: DISCONN” LDC is disconnected to GPRS and COMMUNICATION SERVER

1. The GPRS signal may be low - fit a high gain antenna and power down the LDC. After 30 seconds power up the LDC.
2. There is no network available - swap the SIM card to another network (EE, O2 or Vodafone) **record SIM number**

“G: DIALUP” LDC is trying to connect to the communication server

1. The GPRS signal may be low - fit a high gain antenna and power down the LDC. After 30 seconds power up the LDC.
2. There is no network available - swap the sim card to another network (EE, O2 or Vodafone) **record SIM number**

“G: CONN” LDC is connected to COMMUNICATION SERVER and working

“READY” This means LDC is fully operational and has communicated.

Please phone Orsis Support Team on 01423 537088 to check and confirm the connection.

LDC A1700 mains powered

The A1700 LDC can also be used with the Elster A1140 WC & CT meters.

The LDC is mains powered and requires power via a 240V fused connection unit.

Where RF is being utilised, this LDC must be installed before any other meters, otherwise a successful RF connection cannot be guaranteed.



Equipment material list Elster A1140 meter installation

Equipment	Purpose
A1140 Meter	To record generation / export
A1140 meter to LDC cable	Fitted to the A1140 Meter's RJ and the LDC's 9 pin "D" type socket which provides power and data connection to the LDC
LDC – A1140	This collects the reads sent from the host A1140 meter via RF transmissions.
LDC – mains powered	This collects the reads sent from the meters via RF transmissions
GSM Antenna- to attach to LDC	This is screwed in to the LDC alongside the serial cable and transmits the reads collected by the LDC via GPRS.

Part	Product Description	Connection requirements	Description	Notes
Elster A1140/A1140CT	Electricity meter (Single or three -phase)	Live and neutral (supply and load)	Connections from LHS of meter are L1 Supply, L1 Load, L2 Supply, L2 Load, L3 Supply, L3 Load, Neutral In, Neutral Out	If used for single phase then only L1 and neutral connections are used. Where pulse is enabled and utilised the connection points are above the RJ connection point + to left – to right
			No display on the meter?	Firstly, check that power is on. If not, switch power on. If power is on and there is still no display then change the meter.
			How often should test display scroll?	Automatic cycling every 4 seconds.
			What should the display sequence be reading?	There should be 2 display readings – Test (all segments of LCD illuminated) Total kWh register (6 digits)

Installation check list

A1140 Meter

☐

A1140 Cable

☐

LDC

☐

GPRS Antenna

☐

Commissioning Phase

It is essential that the commissioning engineer contacts the Orsis support team to confirm the communications paths are operational between the Meter and LDC via GPRS **BEFORE** leaving site.

The metering system will not be deemed operational until Orsis support staff confirm all communications paths are connected.

Please phone Orsis Support Team on 01423 537088 to check and confirm the connection.

CT meter commissioning phase

For a CT installation it is essential that a full commissioning check is performed to confirm the meter is operating correctly. The meter is sensitive to connections and L1, L2 and L3 must be connected in the correct order on the meter (from left to right).

The commissioning sheet on the following page (Appendix A) can be used to confirm correct meter operation.

The metering system will not be deemed operational until Orsis support staff confirm all communications paths are connected.

Please phone Orsis Support Team on 01423 537088 to check and confirm the connection.



LV CT Panel Meter Commissioning Form

Appendix A

Voltages

L1-N		V
L2-N		V
L3-N		V

L1-L2		V
L2-L3		V
L3-L1		V

Phase Rotation	
----------------	--

Currents

Primary

L1:		A
L2:		A
L3:		A

Secondary

L1:		A
L2:		A
L3:		A

Calculated ratio

Ratio:	
Ratio:	
Ratio:	

Current Transformer Ratio:	
----------------------------	--

Power

Calculated

L1:		KVA
L2:		KVA
L3:		KVA
Total:		KVA

Metered

L1:		KVA
L2:		KVA
L3:		KVA
Total		KVA

Panel Meter Serial No:	
------------------------	--

Pulse Value		KWh
-------------	--	-----

Pulse Width:	
--------------	--

Current Transformer Ratio:	
----------------------------	--

Meter Total KWh:	
------------------	--

COAP Total KWh:	
-----------------	--

Time:	
-------	--

Date:	
-------	--

Operator:	
-----------	--